



## Large Capacity Fully Automatic Stationary Hzs90 Concrete Batching Plant With Cement Silo 50 Ton-200 Ton

Our Product Introduction

for more products please visit us on [sunnyconcretebatchingplant.com](http://sunnyconcretebatchingplant.com)

### Basic Information

- Place of Origin: Hunan
- Brand Name: SUNNY
- Model Number: HSZ90
- Minimum Order Quantity: 1 set
- Price: USD 110000-150000/ SET
- Packaging Details: container
- Delivery Time: 25-30 days
- Payment Terms: L/C, T/T, D/P, Western Union, MoneyGram
- Supply Ability: 20 Set/Sets per Month



### Product Specification

- Maaterial: Cement, Crushed Stone, Sands And So On
- Application: Building Works,Construction Projects,bridges,docks,airport
- Control System: Automatic PLC Control,totally Automatic
- Productivity:  $\leq 90\text{m}^3/\text{h}$
- Mixer: JS1500 Twin-shaft Concrete Mixer
- Warranty: 12 Months
- Condition: New
- After-sales Service Provided: Engineers Available To Service Machinery Overseas,Online Support,Video Technical Support,Field Installation,commissioning And Training
- Highlight: **fully automatic concrete batching plant, Concrete Batching Plant With Cement Silo, 50 Ton-200 Ton concrete batching plant**



## Product Description

### Ready Mix Concrete Batching Plant 90m3 /H Precast Concrete Plant Equipment HZS90 Manufacturer Concrete Batch Plant concrete batching plant

The HZS90 batching plant is equipped with advanced weighing systems that ensure precise measurement and dosing of materials. With precision sensors and load cells, these systems accurately weigh aggregates, cement, water, and additives. This precise control of material ratios guarantees consistent and high-quality concrete mixes. Installation and setup of the HZS90 batching plant are made easy with its modular design. The plant consists of multiple modular units that can be quickly assembled and disassembled, reducing setup time and facilitating transportation and relocation. This modular design also allows for flexibility in configuration to meet specific project requirements.

Name of parameter	HZS60	HZS90	HZS120	HZS180	HZS240
Theoretical productivity	60 M3/h	90 M3/h	120 M3/h	180 M3/h	240m³/h
Model of mixer	JS1000	JS1500	JS2000	JS3000	JS4000
Mixing motor power	2x18.5Kw	2x30Kw	2x37Kw	2x55Kw	2*75Kw
Cycle period	60s	60s	60s	60s	60s
Volume of mixer	1000L	1500L	2000L	3000L	4000L
Unloading height	4.0m	4.0m	4.0m	4.0m	4.0m
Measuring range and precision of aggregate	(600-2000)≤±2%	(700-2400)≤±2%	(1000-3600)≤±2%	(1600-4800)≤±2%	(1600-4800)≤±2%
Measuring range and precision of cement	(300-1200)≤±1%	(300-1200)≤±1%	600-1800)≤±1%	(800-2400)≤±1%	(800-2400)≤±1%
Measuring range and precision of coal ash	(200-600)≤±1%	(200-600)≤±1%	(300-900)≤±1%	(400-1200)≤±1%	(400-1200)≤±2%
Measuring range and precision of water	200-600)≤±1%	(200-600)≤±1%	(200-700)≤±1%	(360-1200)≤±1%	(360-1200)≤±1%
Measuring range and precision of admixture	20-60)≤±1%	(20-60)≤±1%	(30-100)≤±1%	(36-120)≤±1%	(36-120)≤±1%



The HZS90 Concrete Batching Plant is a highly efficient and versatile solution for large-scale concrete production, ideal for infrastructure projects, commercial construction, and various civil engineering applications. With a production capacity of 90 cubic meters per hour, this plant is designed to meet the demands of high-performance concrete mixing. Featuring advanced technology such as a twin-shaft mixer, precise weighing systems, and a user-friendly control interface, the HZS90 ensures consistent quality and efficiency in every batch. Its modular design allows for easy installation and adaptability to different site requirements, making it a reliable choice for contractors seeking to optimize their concrete production processes.

#### Q: What kind of products do you have?

1. Stationary concrete batching plant arranges from HZS25 to HZS180.
2. Mobile concrete batching plant.
3. Concrete mixer machine.
4. Portable drum concrete mixer with diesel engine.
5. Spare parts including screw conveyor and bolted cement silo.

#### Q: Are you trading company or manufacturer?

A: We are manufacturer. We can design and manufacturer products with our patent. Welcome to visit us to check it!

**Q: What are the terms of payment in your formal trade?**

A:Normally we can work on T/T term ,L/C term and Alibaba Trade Assurance Order Online .

T/T: 30%T/T prepayment , 70% paid by T/T before delivery.

L/C: 100% irrevocable L/C at sight.



**Hunan Sunny Intelligent Machinery Co.,LTD.**



+86 19118921276



amy@hnsunny.com.cn



sunnyconcretebatchingplant.com

Construction Machinery Supporting Industrial Park, High-tech Zone, Ningxiang City, Hunan Province